

EPG Companies Inc.
1990 County Road 81
Maple Grove, MN 55311

*called Donna Keil
and asked for
actual invoices
10/11/12. She will
e-mail it.
DH*

Phone: 763-424-2613
800-443-7426
Fax: 763-493-4812
www.epgco.com

Quote Number: 14131 Rev Num 1

Page 1 of 5

TO:

Steve Chace
RDG Geoscience & Engineering, Inc.
10360 Sapp Bros. Drive
Omaha NE 68138-4804
USA

Date: 6/18/2012
Expires: 7/18/2012
Reference: RemTrailer
Site: South Yankton, NE
SalesPerson: Jim Bailey

<u>Qty</u>	<u>Part Number / Description</u>	<u>Unit Cost</u>	<u>Your Cost</u>
1	VLR-250-7.5X3 Vacuum Pump Package, ~155 CFM at 12" HG, with Rietschle VLR-250 oilless claw vacuum pump, 7½ HP, 230 V, 3Ø, XP motor, vacuum relief valve, vacuum gauge with isolation valves and tee, dilution air valve with filter silencer, CS-16b condensate filter separator with 3-point level sensor/sight tube, manual drain, 1 HP, 230V, 3Ø, XP condensate pump, Viton seal, check valve, ball valve, sample port, 1/4" discharge access port with plug, and piping and fittings.	\$17,458.00 EA	\$17,458.00
1	OS-8-F Oil/Water Separator, 25 gpm, fiberglass construction, stand mounted with anchor brackets, FLO-PAK media, expanded effluent chamber, high level sensor/sight tube, manual drain, 2" SCH 40 PVC product discharge line, and 2" SCH 40 PVC water discharge line.	\$9,110.00 EA	\$9,110.00
1	LO0200-RT-3F-CD100BF Transfer Tank, 200 gallons, polyethylene, with 2" inlet port, 2" vent, 2" sensor port, and pump out port/drain, strapping bands, 3-point float level sensor, transfer pump, 1/2 HP, 230 V, 3Ø, XP motor, Viton seal, check valve, ball valve, sample port, Blancett B111-110, 1" flow meter, B28SBM-AB display, and piping.	\$4,150.00 EA	\$4,150.00
1	ASC200ACRSD Carbon Vessels (2), 200 lbs. carbon fill each, 10 gpm, poly drums, liquid-phase, hoses with poly quick connect fittings, straps and brackets, sample ports (2), and fittings.	\$2,590.00 EA	\$2,590.00

EPG Companies Inc.

19900 County Road 81
Maple Grove, MN 55311

Phone: 763-424-2613
800-443-7426
Fax: 763-493-4812
www.epgco.com

Quote Number: 14131 Rev Num 1

Page 2 of 5

- | | | |
|---|--|-------------------------------|
| 1 | Series R745-1200
EPG Control Panel, UL listed, 230 V, 3Ø, NEMA 4 enclosure with dead front, inner door, stainless steel drip shield, padlocking handle, and main disconnect, to control 7½ HP vacuum pump, (H)OA switch, green run light, red motor overload light, elapsed time meter (ETM), 7-day cycle timer, intrinsically safe (IS) 3-point condensate level sensor, red high level alarm light, 1 HP condensate pump, (H)OA switch, green run light, red motor overload light, ETM, IS high level sensor for OWS, red high level alarm light, IS product tank full sensor, red high level alarm light, IS 3-point level sensor for transfer tank, red high level alarm light, 1/2 HP transfer pump, (H)OA switch, green run light, red motor overload light, ETM, common alarms reset push button, and power for exhaust fan, heater, and lights. | \$7,240.00 EA \$7,240.00 |
| 1 | TRL
Enclosed Trailer, 8.5'X18'X6.5', blue exterior, 2-3,500 lb. axles, double back door, insulated walls, ceiling, and floor, plywood walls, luan ceiling liner, 2 sets-scissor jacks, louver vents, XP exhaust fan and thermostat, XP and heater and thermostat, XP lights and switch, XP conduit, wire, and seal-offs, mounting and wiring control panel on outside front, wall and ceiling penetrations, fasteners, mounts, and mounting, piping, and wiring of all equipment. | \$19,341.00 EA \$19,341.00 |
| 1 | TFS-SJ25P
Tank Full Sensor, 2" MNPT, with 25' of SJ cord. For product tank outside by others. | \$245.00 EA \$245.00 |

Total amount quoted: \$ 60,134.00

*This rate
is 5.5%*

Tax 3307.37

63441.37