

EPG Companies Inc.

19900 County Road 81
Maple Grove, MN 55311

Phone: 763-424-2613
800-443-7426
Fax: 763-493-4812
www.epgco.com

Quote Number: 6722 Rev Num 1

Page 1 of 2

TO:

Steve Chace
RDG Geoscience & Engineering, Inc.
10360 Sapp Bros. Drive
Omaha NE 68138-4804

Date: 12/2/2004
Expires: 1/1/2005
Reference: SVEtrailer
Site: Nebraska City, NE
SalesPerson: Jim Bailey

We are pleased to present the following revised remediation equipment quote for your project in Nebraska City, NE.

<u>Qty</u>	<u>Part Number / Description</u>	<u>Unit Cost</u>	<u>Your Cost</u>
1	<p>SVE Trailer Vapor Extraction Trailer, 8.5'X12'X8'-6", square body style, white exterior, with dual axles, double rear doors, stabilizer jacks, insulated walls, ceiling, and floor, plywood lined, aluminum tread plate floor, louver vents, explosion-proof (XP) exhaust fan with thermostat, XP light and switch, XP heater with thermostat, and XP conduit and wiring. Includes mounting and wiring control panel on outside front of trailer, and mounting and wiring all equipment.</p> <p>SVE Package, 1000 ACFM at 6" HG (plus 1 PSI inlet piping and 0.2 PSI discharge silencer losses), with Roots 615 URAI positive displacement blower, 25 HP, 230 V, 3PH, XP motor, vacuum relief valves, vacuum gauge-LF, dilution air valve, inlet/discharge sample ports, CS-30 condensate filter separator, high level sensor-SS with galv. steel housing, discharge silencer, belts, sheaves, stand, belt guard, piping, and steel inlet manifold with 5 ea. 4" Rotron aluminum flow meters (90-450 SCFM), vacuum gauges-LF, steel sample ports, and steel flow control valves.</p> <p>EPG Series R715 Controller, UL listed, 230 V, 3PH, NEMA 4 enclosure, with dead front, inner door, stainless steel drip shield, padlocking handle, and main disconnect, to control SVE blower, HOA switch, green run light, elapsed time meter, 7-day cycle timer, intrinsically safe high condensate level sensor, red alarm light, 15A GFCI on inner door, and power for fan, light, and heater.</p>	\$39,960.00 EA	\$39,960.00

Includes freight to the site with off-loading by others.

Total amount quoted \$ 39,960.00