

EPG Companies Inc.

19900 County Road 81
Maple Grove, MN 55311

Phone: 763-424-2613
800-443-7426
Fax: 763-493-4812
www.epgco.com

Quote Number: 13296 Rev Num 1

Page 1 of 5

TO:

Mark Liska
RDG Geoscience & Engineering, Inc.
10360 Sapp Bros. Drive
Omaha NE 68138-4804
USA

Date: 7/13/2011
Expires: 8/12/2011
Reference: RemTrailer
Site: Osmond Mini Mart
SalesPerson: Jim Bailey

<u>Qty</u>	<u>Part Number / Description</u>	<u>Unit Cost</u>	<u>Your Cost</u>
1	UP6-10TAS Compressor Package, Ingersoll-Rand, 38 CFM rated, Total Air System, low sound enclosure, rotary screw, with 10 HP, 230 V, 3Ø, ODP motor, NEMA 1 starter, pressure switch, hour meter, 80 gallon tank, electronic tank drain, particulate filter, coalescing oil filter, cycling refrigerated dryer, 3/4" discharge solenoid valve, compressor base mounts, conduit, wiring, and piping.	\$9,081.00 EA	\$9,081.00
1	OS-12-F Oil/Water Separator, 36 gpm, fiberglass construction, stand mounted with anchor brackets, FLO-PAK media, expanded effluent chamber, high level sensor/sight tube, manual drain, 2" SCH 80 PVC product discharge line, and 2" SCH 80 PVC water discharge line. Product tank and high level sensor mounted and piped outside of trailer provided by others.	\$10,750.00 EA	\$10,750.00
1	LO0200-RT-3F-CD100BF Transfer Tank, 200 gallons, polyethylene, with 2" inlet port, 2" vent, 2" sensor port, and pump out port/drain, strapping bands, 3-point float level sensor, transfer pump, 1/2 HP, 230 V, 3PH, explosion-proof (XP) motor, Viton seal, check valve, ball valve, sample port, and fittings.	\$2,945.00 EA	\$2,945.00
1	VES-RT7.5 Vapor Extraction Package, with Rotron EN858 regenerative blower, 7½ HP, 230 V, 3Ø, XP motor, vacuum relief valve, vacuum gauge with isolation valves and tee, dilution air valve with filter silencer, CS-16b condensate filter separator with 3-point level sensor/sight tube, manual drain, 1 HP, 230V, 3PH, XP condensate pump, Viton seal, check valve, ball valve, sample port, discharge silencer, 1/4" discharge access port with plug, and piping and fittings.	\$10,472.00 EA	\$10,472.00

EPG Companies Inc.

19900 County Road 81
Maple Grove, MN 55311

Phone: 763-424-2613

800-443-7426

Fax: 763-493-4812

www.epgco.com

Quote Number: 13296 Rev Num 1

Page 2 of 5

- | | | |
|---|---|----------------------------|
| 1 | STAT 180-5
Low-Profile Air Stripper, STAT 180, 5-Tray, stainless steel, demister, 7½ HP, 230 V, 3Ø, XP blower, in-line inlet filter, inlet silencer, XP low pressure switch, pressure gauge with isolation valves and tee, flow control valve, 3-point sump level sensor/sight tube, manual drain, 1/2 HP, 230V, 3PH, XP discharge pump, Viton seal, check valve, ball valve, sample port, Blancett turbine flow meter with battery powered monitor, 5-50 gpm, and piping. Includes support for blower filter and silencer as needed. | \$33,894.00 EA \$33,894.00 |
| 1 | Series R745-525
EPG Control Panel, UL listed, 230 V, 3Ø, NEMA 4 enclosure with main disconnect, padlocking handle, and lights and switches in the outer door, fused power on-off switch for 10 HP air compressor, to control pneumatic pumps with solenoid valve, open-close-auto switch, green open indicator light, intrinsically safe (IS) product tank full sensor, red high level alarm light, IS high level sensor for OWS, red high level alarm light, IS 3-point level sensor for transfer tank, red high level alarm light, 1/2 HP transfer pump, (H)OA switch, green run light, red motor overload light, elapsed time meter, 7.5 HP air stripper blower, HOA switch, green run light, red motor overload light, elapsed time meter, off-delay timer, low air pressure switch, red low air pressure alarm light, fault on-delay timer, IS air stripper sump 3-point level sensor, red high level alarm light, 1/2 HP discharge pump, (H)OA switch, green run light, motor overload light, elapsed time meter, 7.5 HP vapor extraction blower, HOA switch, green run light, red motor overload light, elapsed time meter, 7-day cycle timer, IS condensate separator 3-point level sensor, red high level alarm light, 1 HP condensate pump (to OWS), and common alarms reset push button. Includes power distribution and transformer for back room fan, lights, and heater, and front room fan, light, heater, duplex outlet (for refrigerated dryer and tank drain), and 15A duplex GFCI convenience outlet. | \$12,810.00 EA \$12,810.00 |

EPG Companies Inc.

19900 County Road 81
Maple Grove, MN 55311

Phone: 763-424-2613

800-443-7426

Fax: 763-493-4812

www.epgco.com

Quote Number: 13296 Rev Num 1

Page 3 of 5

1	TRL	\$25,183.00 EA	\$25,183.00
---	-----	----------------	-------------

Enclosed Trailer, 8.5'X24'X9.5', blue, 2-3,500 lb. axles, double door in back equipment room, 36" door in ~5' front control/compressor room, insulated walls, ceiling, and floor, plywood walls, luan ceiling liner, 3 sets-scissor jacks, louver vents in both rooms, XP and non-XP exhaust fans and thermostats, XP and non-XP heaters and thermostats, XP lights and switch, non-XP fluorescent light and switch, conduit, wire, duplex outlet front room (refrigerated dryer and tank drain) and duplex 15A GFCI convenience outlet, wall and ceiling penetrations, fasteners, mounts, and control panel support, and mounting, piping, and wiring of all equipment.

Total amount quoted \$ 105,135.00

Thank you for allowing us to quote on this project. All prices quoted are based on information supplied for bidding and our interpretation of that information along with our recommendations and/or changes for fabrication. Prices are subject to review and possible adjustment for any changes made that deviate from our outline given.

Services such as start up supervision, operator training, and testing services are available at our standard rate in effect at the time services are provided, plus documented travel and lodging expenses. See Bulletin 31201 for our current rates. Scheduling requires minimum 10 business days notice and is subject to availability.

Prices quoted do not include freight F.O.B. our dock in Maple Grove, MN. Prices do not include any applicable taxes. See Bulletin 3406 regarding Terms of Sale subject to credit approval, and Bulletin 0200c describing our Limited Warranty. Currently, this equipment would ship in approximately twelve (12) to fourteen (14) weeks from date of approved order. If you have any questions or would like to place an order, please let me know.

Sincerely,
EPG Companies Inc.



Jim Bailey
Applications Specialist